

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-23138-00-00
Spot: SWNW SW Sec/Twnshp/Rge: 10-25S-13E
1485 feet from S Section Line, 330 feet from W Section Line
Lease Name: WEBBER Well #: W-4
County: GREENWOOD Total Vertical Depth: 1551 feet

Operator License No.: 5370
Op Name: SOULE, RICHARD A.
Address: 822 E RIVER
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1551	0	
SURF	7	40	0	

\$ 50.41

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/30/2007 4:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' cement plug @ 1500' 50' cement plug @ 700' 150' cement plug to surface.

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/30/2007 6:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report: _____ Perfs: _____

squeeze bottom plug to 1500' 15 sxs cement, squeeze 10 sxs cement @ 700' squeeze 20 sxs cement @ 150' to surface 20 sxs cement, gel spacers between cement plugs.

**RECEIVED
KCC DISTRICT #3**

SEP 10 2007 MH

CHANUTE, KS

INVOICED
DATE 9/20/07
INV. NO. 2008060440

Remarks:
Plugged through: CSG

District: 03

Signed Mike Hoff
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 14 2007
CONSERVATION DIVISION
WICHITA, KS

SEP 14 2007

CONSERVATION DIVISION
WICHITA, KS

bd

Corrected spot location

State of Kansas

CORRECTION

Expires: 10/25/84

NOTICE OF INTENTION TO DRILL

4-27-84

Starting date 5 6 84
Month Day Year

API Number 15-
SW NW SW Sec. 10 T 25 S, R 13 ~~XXXXX~~ East

073-23138

Operator license # 5596

1485 ft. from ~~XXX~~ S line of section S.C. 5-30-84 40'
330 ft. from ~~W~~ line of section 711

Operator name & address Bird & Hanley
R. 1, Box 82
Toronto, Ks. 66777

Nearest lease or unit boundary line 165 feet

County Greenwood Webber Well # W-4

Contact person Bob Hays

Surface pipe by alternate 1 _____ or 2 X

Phone 316 637/2340

Domestic well within 330 ft. X yes; Municipal well within one mile _____ yes
X no; _____ no

Contractor license # 5913

Depth of fresh water 25 feet

Contractor name & address Alco Drlg. Co.
R. 3
Iola, Ks. 66749

Lowest usable water formation Quaternary Douglas GR

Depth to bottom of usable water 150 400 feet

Surface pipe to be set 40 feet

Conductor pipe if any required None feet

Type equipment: rotary X air _____ cable _____

Ground surface elevation 950 feet MSL

Well drilled for: oil X gas _____ SWD _____

Est. total depth 1400 feet

Inj _____ OWWO _____

Well class: infield X pool ext _____ wildcat _____

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specs.
Date 4/26/84 Signature of operator or agent [Signature] Title Mgr.

Date received 4-25-84

To be filed with Kansas Corporation Commission SE NESW
5 days prior to commencing well.

Card to be typed Kwas: 2330 FWL