

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

Please TYPE Form and File ONE Copy

15-073-19680-0000

API # 15-5-26-26 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 5-26-26

Well Operator: R.R. Abderhalden KCC License #: 5394

Address: 100 S. Main, Suite 510 (Owner/Company Name) City: Wichita (Operator's)

State: Kansas Zip Code: 67202 Contact Phone: (316) 262-3411

Lease: Demalorie-Sowder Well #: 50 Sec. 12 Twp. 22 S. R. 10 East West

Spot Location / QQQQ County: Greenwood

1650 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

990 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 1704 Cemented with: NA Sacks

Production Casing Size: 6 5/8 Set at: 2060 Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perf: 1223-26 (squeezed). Perf: 2043-46. The 6 5/8 casing has been cemented to surface.

Elevation: 1219 (G.L. / K.B.) T.D.: 2145 PBTD: 2137 Anhydrite Depth: _____

Condition of Well: Good Poor Casing Leak Junk in Hole (Stone Corral Formation)

Proposed Method of Plugging (attach a separate page if additional space is needed): Dump 50 ft. sand over perforations. Dump 50 ft. cement on top of sand. Run tubing to 150 ft. and cement to surface.

RECEIVED
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? NA

OCT 10 2007

CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dwain Stout

100 S. Main, Suite 510, Wichita, Kansas 67202 Phone: (316) 640-9072

Address: _____ City / State: _____

Plugging Contractor: K.E. Snyder Company LLC KCC License #: 32147

Address: Box 107, Hamilton, KS 66853-0107 Phone: (620) 678-3613 (Contractor's)

Proposed Date and Hour of Plugging (if known?): November, 2007

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 10-9-07 Authorized Operator / Agent: R.R. Abderhalden

R.R. Abderhalden
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

J. E. Fechter #3
 Prairie Oil & Gas Company
 Elevation:
 Rig Com.
 Rig Comp. 5/2/26.
 Rig Cont. D. E. Bridgman
 I. P. 40 Bbls after shot.

Sec. 12-22-10, Greenwood County, Kansas
 Independent Kansas
 Loc'd. 330' from E L & 990' from S L
 Drlg. Com. 5/6/26.
 Drlg. Comp. 5/26/26.
 Drlg. Cont. J. J. Muth.
 Shot 5/240 Qts; 5-27-26; 2082' to 2130'

Sand - Record

Sand, broken	2054	2060	
Sand, oil	2060	2130	121962

Casing - Record

Size	Wt	Jts	Placed In	Pulled Out	Left In
12 1/8"			363' 10"	All	None
10"			1154' 4"	"	"
8 1/4"			1703' 8"	None	All
6 5/8"			2060'	"	"
2" Tubing					2136
5/8" Rods					2120

Formation - Record

Yellow clay	0	10	First show of oil 2082' to 2090'.
Slate, & shells	15	25	Move oil 2111 to 1116'.
Slate, black	25	50	Bottom of sand 2130'.
Slate, white	25	75	
Lime, white	10	85	
Slate, black	50	135	
Slate, white	40	175	
Lime, white	10	185	
Slate, white	15	200	
Lime, white	10	210	
Slate, black	10	220	
Lime, white	10	230	
Slate, black	130	360	
Slate, white, 12 1/8" @ 363' 10"	90	450	
Slate, black	10	460	
Slate, & L. shells	10	470	
Lime	20	490	
Slate	80	570	
Slate & L. shells	130	700	
Slate	65	765	
Lime	5	770	
Slate	20	790	
Lime	10	800	
Slate	190	990	
Lime	10	1000	
Slate	60	1060	
Sand, H. F. W. at 1075'	45	1105	
Slate	5	1110	
Lime	10	1120	
Slate	20	1140	
Lime, 10" Csg @ 1154' 4"	115	1255	
Slate	115	1370	
Slate, black	15	1385	
Lime	165	1545	
Slate	5	1550	
Lime	15	1565	
Slate	110	1675	
Lime	5	1680	
Slate, 8 1/4" Csg @ 1704' 8"	20	1700	
Lime	25	1725	
Slate	50	1775	
Lime, water enough to drill with	35	1810	
Slate	65	1875	
Slate, black	91	1966	
Slate, white	10	1976	
Slate, dark	25	2001	
Sand, broken	7	2008	
Shale	13	2021	
Slate	15	2036	
Shale	10	2046	
Shale, black	8	2054	
6 5/8" Casing at 2060'.			
Sand, broken	6	2060	
Sand	70	2130	
Shale, dark	15	2145	
Total Depth		2145	

RECEIVED
 KANSAS CORPORATION COMMISSION

OCT 10 2007

CONSERVATION DIVISION
 WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

ABDERHALDEN, R. R.
510 HARDAGE CENTER
100 S MAIN
WICHITA, KS 67202

November 02, 2007

Re: DEMALORIE SOWDER #50
API 15-073-19680-00-00
12-22S-10E, 1650 FNL 990 FWL
GREENWOOD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after April 30, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #3
1500 W. 7th
Chanute, KS 67220
(620) 432-2300