

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

15-073-19679-0002

API # 15-~~9-18-52~~ (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 9-18-52

Well Operator: R.R. Abderhalden KCC License #: 5394
(Owner / Company Name) (Operator's)

Address: 100 S. Main, Suite 510 City: Wichita

State: Kansas Zip Code: 67202 Contact Phone: (316) 262-3411

Lease: Demalorie-Sowder Well #: S-6 Sec. 12 Twp. 22 S. R. 10 East West

200' SE - SW - NW - NW Spot Location / QQQQ County: Greenwood

1040 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

161 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # E-3423 Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 13" Set at: 147 Cemented with: 75 Sacks

Production Casing Size: 8 5/8" Set at: 2660 Cemented with: 636 Sacks

List (ALL) Perforations and Bridgeplug Sets: Plug set at 2479". Perf: 1110-1150'

Elevation: 1127 (G.L. / K.B.) T.D.: 3475 PBTD: 2479' Anhydrite Depth: _____

Condition of Well: Good Poor Casing Leak Junk in Hole (Stone Corral Formation)

Proposed Method of Plugging (attach a separate page if additional space is needed): Dump 50' sand over perforations. Dump 50' cement on top of sand. Pull tubing to 150' and cement to surface.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? NA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dwain Stout

Phone: (316) 640-9072

Address: _____ City / State: _____

Plugging Contractor: K.E. Snyder Company, LLC KCC License #: 32147
(Company Name) (Contractor's)

Address: Box 107, Hamilton, KS 66853-0107 Phone: (620) 678-3613

Proposed Date and Hour of Plugging (if known?): November, 2007

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10-2-07 Authorized Operator / Agent: R.R. Abderhalden

R.R. Abderhalden RECEIVED
(Signature) KANSAS CORPORATION COMMISSION

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

OCT 04 2007

CONSERVATION DIVISION
WICHITA KS

Formation Record

Lease: D & S Unit (Phillips Petroleum Co.) Well No. 8-6
 Location: 1040' fr/ML, 161' fr/ML, NW/4 Sec. 12-22E-10E, Greenwood County, Kansas

FROM	TO	Formation	REMARKS
0	7	Topsoil	Elevation 1227' Od, RKB 4' above ground.
7	11	Lime	
11	25	Shale	
25	30	Lime	
30	40	Shale	
40	45	Lime	
45	65	Shale	
65	75	Lime	
75	80	Shale	
80	85	Lime	
85	105	Shale	13" OD csg set @ 117' GM w/75 sacks.
105	110	Lime	
110	125	Shale	
125	130	Lime	
130	135	Shale	
135	140	Lime	
140	145	Shale	
145	1470 M	Lime	
147	GM 162RKB	Shale	
162	397	Shale and sand	
397	552	Lime and shale	
552	733	Shale and sand	
733	832	Shale and lime	
832	1047	Shale, sand and lime streaks	
1047	1200	Shale and lime	
1200	1245	Lime	
1245	1410	Lime and shale	
1410	1541	Lime	
1541	1611	Lime and shale	
1611	1714	Shale, sand and lime streaks	
1714	1818	Sandy shale	
1818	1961	Lime and shale	
1961	2021	Lime and sand	
2021	2095	Lime, shale and sand	
2095	2175	Shale and sand	
2175	2206	Lime and shale breaks	
2206	2497	Lime	
2497	2566	Lime and shale	
2566	2616	Shale, sand and lime	8-5/8" OD csg set @ 2600 RKB w/636 sacks.
2616	2640	Lime and sand	2660
2640	2665	Lime, chert and sand	
2665	2753	Shale and sand	
2753	3435	Lime	
3435	3475	Sand and granite	

3475 TD RKB

Well completed: 9-19-52.

Well started pumping: 11-12-52.

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 04 2007

CONSERVATION DIVISION
WICHITA, KS



Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

ABDERHALDEN, R. R.
510 HARDAGE CENTER
100 S MAIN
WICHITA, KS 67202

November 02, 2007

Re: DEMALORIE SOWDER #S-6
API 15-073-19679-00-00
12-22S-10E, 1040 FNL 161 FWL
GREENWOOD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after April 30, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #3
1500 W. 7th
Chanute, KS 67220
(620) 432-2300