

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

15-073-19678-0000

API # 15 - 7-12-26 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 7-12-26

Well Operator: R.R. Abderhalden KCC License #: 5394  
(Owner / Company Name) (Operator's)

Address: 100 S. Main, Suite 510 City: Wichita

State: Kansas Zip Code: 67202 Contact Phone: (316) 262-3411

Lease: Demalorie-Sowder Well #: 54 Sec. 12 Twp. 22 S. R. 10  East  West

SW SE NW Spot Location / QQQQ County: Greenwood

1310 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1650 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8 Set at: 1692 Cemented with: NA Sacks

Production Casing Size: 6 5/8 Set at: 2035 Cemented with: NA Sacks

List (ALL) Perforations and Bridgeplug Sets: \_\_\_\_\_

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 10 2007

Elevation: 1219 ( G.L. /  K.B.) T.D.: 2132 PBDT: \_\_\_\_\_ Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole  
CONSERVATION DIVISION WICHITA, KS

Proposed Method of Plugging (attach a separate page if additional space is needed): Dump san on bottom and fiil 50ft in 6 5/8 casing. Dump 50 ft cement on sand. Shoot off 6 5/8 at 1650 ft and pull. Shoot off 8 5/8 casing above Douglas sand, pull and set a 50 ft cement plug above Douglas sand. Run

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No tubing to 150 ft and cement to surface.  
If not explain why? NA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dwain Stout

100 S. Main, Suite 510, Wichita, Kansas 67202 Phone: (316) 640-9072

Address: \_\_\_\_\_ City / State: \_\_\_\_\_

Plugging Contractor: K.E. Snyder Company LLC KCC License #: 32147  
(Company Name) (Contractor's)

Address: Box 107, Hamilton, Kansas 66853-0107 Phone: (620) 678-3613

Proposed Date and Hour of Plugging (if known?): November, 2007

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 10-9-07 Authorized Operator / Agent: R.R. Abderhalden  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

WELL LOG

LEASE DeMalorie Sowders WELL NO. 54  
 LOCATION: 330' N of SL & 330' E of WL SE/4 NW/4 Sec. 12-T-22-R10E, Greenwood County, Kans.  
 SURFACE ELEVATION 1219 DATE COMPLETED 7-12-26

CASING RECORD:

<u>Size</u>	<u>Set At</u>	<u>Pulled</u>	<u>SHOT: Quarts</u>	<u>Initial Production</u>
12 $\frac{1}{2}$	500	500		
10	1175	1175	220	125
8 $\frac{1}{2}$	1692			
6 5/8	2035			
BARTLESVILLE SAND:	Top <u>2073</u>		Base <u>2129</u>	T.D. <u>2132'</u>

Formation:

<u>Formation:</u>	<u>Depth:</u>	<u>Formation:</u>	<u>Depth:</u>
soil	5	shale	1400
slate	20	lime	1600
lime	30	shale	1690
slate	75	lime	1695
lime	100	shale	1710
slate	110	lime	1715
lime	125	shale	1725
shale	130	lime	1735
lime	140	shale	1785
shale	175	lime	1795
lime	195	slate	1815
shale	205	lime	1820
lime	240	slate	1835
shale	325	lime	1840
lime	340	shale	1860
shale	385	lime	1865
lime, 1 BW	410	shale	1900
shale	475	lime	1910
lime	515	shale, 2 BW	1910
shale	565	shale	2055
lime	595	sand and shale	2073
slate	610	sand, oil	2090
lime	615	<del>XXXXX</del> sand	2129
shale	630	shale	2132
lime	640		
shale	665		
lime	675		
shale	700		
lime	720		
shale	760		
lime	770		
shale, 1 BW 775	785		
lime	815		
lime	855		
slate	900		
lime	915		
shale	1005		
shale HFW	1070		
sand	1100		
lime	1110		
sand	1130		
lime	1140		
sand	1155		
lime	1165		
slate	1175		
lime	1192		
shale	1195		
lime	1205		
shale	1210		
lime	1275		
shale	1380		
lime	1390		

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 10 2007

CONSERVATION DIVISION  
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

ABDERHALDEN, R. R.  
510 HARDAGE CENTER  
100 S MAIN  
WICHITA, KS 67202

November 02, 2007

Re: DAMALORIE SOWDER #54  
API 15-073-19678-00-00  
12-22S-10E, 1310 FNL 1650 FWL  
GREENWOOD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after April 30, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #3  
1500 W. 7th  
Chanute, KS 67220  
(620) 432-2300