

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21274-00-00
Spot: SESENW Sec/Twnshp/Rge: 7-9S-18W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: WERNER Well #: 5
County: ROOKS Total Vertical Depth: 3637 feet

Operator License No.: 33699
Op Name: T-N-T ENGINEERING, INC.
Address: 3711 MAPLEWOOD STE 201
WICHITA FALLS, TX 76308

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3513	0	w/130 sxs cmt
SURF	8.625	208	0	w/140 sxs cmt

118.20

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/11/2007 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: RANDY WEIGEL Company: TNT ENGINEERING, INC. Phone: (785) 737-3736

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
Operator elected to use all cement.
Plugging out lease.
DV Tool at 1455' w/370 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/11/2007 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:
Ran tubing to 3338'. Basic Energy Service pumped 125 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1419'. Basic Energy Service pumped 150 sxs cement with 300# hulls - cwc. PTOH. Topped off 5 1/2" casing with 35 sxs.
Hooked up to backside-instant 500#.

Perfs:

Top	Bot	Thru	Comments
3363	3367		
3326	3329		
3264	3270		
3229	3233		

INVOICED
DATE 10/22/07
INV. NO. 200 8060644

Remarks: BASIC ENERGY SERVICE.
Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

OCT 16 2007

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3
OCT 18 2007
CONSERVATION DIVISION
WICHITA, KS

PKT

ENERGY RESERVES GROUP, INC.

925 PATTON ROAD

GREAT BEND, KS 67530

#5 WERNER

7-9-18W
SE SE NW

CONTR EMPHASIS OIL OPERATIONS CTY. ROOKS

GEOL GERALD WEHRLI

FIELD BARRY SE

E 2050 KB CM 4/1/81 CARD ISSUED 7/16/81 IP P 9 BOPD & 89

+	+	+
+	•	+
+	+	+

API 15-163-21,274

BWPD
LANS 3229-3367 OA

LOG	TOPS	DEPTH	DATUM
ANH		1445	+ 605
B ANH		1485	+ 565
TOP		2975	- 925
HEEB		3187	-1137
TOR		3209	-1159
LANS		3228	-1178
B KC		3437	-1387
LTD		3471	-1421
*ARB		3483	-1433
RTD		3637	-1587
*SMP TOP			

8-5/8" 208/140sx, 5 1/2" 3513/130sx,
DV TOOL @ 1455/370sx

DST (1) 3212-3272/30-60-60-120, REC
40' DM, SIP 682-624#, FP 42-51/
51-59#, HP 1765-1748#

DST (2) 3307-3433/30-60-60-120, REC
270' DM, SIP 431-431#, FP 93-186/
186-262#, HP 1866-1798#

DST (3) 3469-3478/30-60-60-105, REC
15' DM, SIP 76-76#, FP 17-34/
34-42#, HP 1933-1916#

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

NOTE: ORIGINAL LOC WAS 7-19-18W
(OVER)