

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-20898-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 31-32S-6E  
1022 feet from S Section Line, 1720 feet from E Section Line  
Lease Name: WERNER Well #: 3  
County: COWLEY Total Vertical Depth: 3150 feet

Operator License No.: 5394  
Op Name: ABDERHALDEN, R. R.  
Address: 510 HARDAGE CENTER 100 S MAIN  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3149		75 SX
SURF	8.625	170		100 SX

102.38

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/04/2007 8:00 AM  
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.  
Proposal Rcvd. from: DWAIN STOUT Company: R.R.A., INC. Phone: (316) 262-3411

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE  
Date/Time Plugging Completed: 09/27/2007 2:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

CIRCULATED HOLE CLEAN @ 1850', SANDED BACK @ 1800', DUMP BAILED 4 SXS CEMENT ON TOP. SHOT 4-1/2" CSG @ 1649', LAYED DOWN 50 JTS 4-1/2" CSG (1649'), 9-27-2007, RIH W/TBG @ 350', R.R.A. MIXED & PUMPED 130 SXS COMMON CEMENT TO SURFACE. CEMENT CIRCULATED. P.A. COMPLETE 1400, 9-27-2007. NO CEMENT TICKET #.

Perfs:

Top	Bot	Thru	Comments
3124	3130		
3070	3074		
3052	3056		
1857	1869		NEW PERF.

INVOICED

DATE 10/23/07

INV. NO. 2008060655


RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 22 2007  
CONSERVATION DIVISION  
WICHITA KS

Remarks: -096.81216,37.21809, PERFS 3052'-3130', PBSD 1890', 1857'-69'

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

