

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20251-00-01
Spot: NWSESW Sec/Twnshp/Rge: 17-31S-6E
675 feet from S Section Line, 3924 feet from E Section Line
Lease Name: BLANCHAT Well #: 1
County: COWLEY Total Vertical Depth: 2975 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		2793		
PROD	4.5	2975	1017	50 SX
SURF	8.625	304		100 SX

96-69

Well Type: EOR UIC Docket No: E16342.3 Date/Time to Plug: 09/20/2007 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 938-2943

Proposed
Plugging
Method:

AS PER KCC RULES & REGS. NOTE: D. KRUEGER'S SPOT LOCATION IS: SWSESW @ 635' S & 3848' E.

Plugging Proposal Received By: _____ WitnessType: PARTIAL
Date/Time Plugging Completed: 09/20/2007 2:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2700', DUMP BAILED 4 SXS CEMENT ON TOP. SHOT 4-1/2" CSG @ 1021', LAYED DOWN 31 JTS 4-1/2" CSG (1021'). 9-20-2007, RIH W/TBG @ 360', BEAR PETROLEUM MIXED & PUMPED 95 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P.A. COMPLETE 1400 PM 9-20-2007. CEMENT TICKET #32411. 10-05-2007, RIH W/TBG @ 125', BEAR PETROLEUM MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT TICKET C-32411. CEMENT CIRCULATED TO SURFACE. DOCKET #E-16342.

Perfs:

Top	Bot	Thru	Comments
2916	2922		
2879	2885		
2842	2849		

INVOICED
DATE 10/23/07
INV. NO. 2008060657

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 22 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: -096.80189,37.34682, PERFS 2842'-49', 2879'-85', 2916'-2922'

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

PK