

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20374-00-00
Spot: SESESE Sec/Twnshp/Rge: 7-31S-6E
332 feet from S Section Line, 142 feet from E Section Line
Lease Name: RISING A Well #: 1
County: COWLEY Total Vertical Depth: 2991 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------------------|
| PROD | 4.5 | 2990 | | 75 SX |
| SURF | 8.625 | 180 | | 125 SX <u>97.21</u> |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2007 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/05/2007 1:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2730', DUMP BAILED 5 SXS CEMENT ON TOP. SHOT 5-1/2" CSG @ 954', LAYED DOWN 30 JTS 5-1/2" CSG. 10-5-2007, RIH W/TBG @ 350', BEAR PETROLEUM MIXED & PUMPED 200 SXS 60/40 POZMIX 4% GEL TO SURFACE. P.A. COMPLETE 1330 PM 10-5-2007. CEMENT TICKET #C-32592.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2900 | 2906 | | |
| 2881 | 2890 | | |

INVOICED
DATE 10/23/07
INV. NO. 2008060657

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 22 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: -096.80702.37.36053, PERFS 2881'-90', 2900'-06'

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

PKT