

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21761-00-01
Spot: W2NWSE Sec/Twnshp/Rge: 15-21S-7W
1581 feet from S Section Line, 2315 feet from E Section Line
Lease Name: ENGELLAND B Well #: 1
County: RICE Total Vertical Depth: 3479 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY, L.L.C.
Address: 1704 LIMESTONE RD
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3479		100 SX
SURF	8.625	200		125 SX

113.07

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/11/2007 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/11/2007 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 3340' AND CAP WITH 5 SX'S CEMENT, CUT OFF CASING @2240' AND PULL TO 1000' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS, PULL CASING TO 550' AND PUMP 35 SX'S CEENT WITH 100#'S COTTON HULLS, PULL CASING TO 250' AND CIRCULATE CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3446	3452		MISS
3424	3436		
3404	3420		
3394	3400		

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 22 2007
CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 10/23/07
INV. NO. 2008060659

Remarks: 60-40 POZ, 4% GEL. QUALITY TICKET #1492. USED 165 SX'S.

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)