

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-23257-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 32-27S-3E  
942 feet from S Section Line, 888 feet from E Section Line  
Lease Name: MORCO UNIT Well #: 2  
County: BUTLER Total Vertical Depth: 2393 feet

Operator License No.: 9913  
Op Name: BULLSEYE PETROLEUM, INC.  
Address: 15820 PLYMOUTH RD  
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2391		
SURF		212		

77.77

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/25/2007 2:00 PM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: RICHARD KANE Company: RICHARD KANE Phone: (918) 214-3471

Proposed Plugging Method: SET CIBP @ 2280' AND CAP W/4 SXS CEMENT, LOAD 4-1/2" CASING AND PRESSURE TO 100# TO INSURE INTEGRITY OF CASING. PERFORATE @ 1500', AND PUMP 50 SXS 60/40 POZMIX 4%. PERFORATE @ 300', AND CIRCULATE BACKSIDE OF 4-1/2" TO SURFACE W/60/40 POZMIX 4% GEL TO SURFACE.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/08/2007 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/CIBP AND SET 2280', DUMP BAILED 4 SXS CEMENT ON TOP. PRESSURED TESTED 4-1/2" CASING @ 150#, HELD OK. RIH PERFORATED 2' W/4 HOLES @ 1200', AND 300', SHUT DOWN. 10-8-2007, RIH W/TBG @ 1200'. CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 25 SXS 60/40 POZMIX 4% GEL, WAITED 1 HR, SWEDGED INTO 4-1/2" CASING AND ESTABLISHED CIRCULATION. CONSOLIDATED MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL TO SURFACE. P.A. COMPLETE 1700 10-8-2007. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #12758.

Perfs:

INVOICED  
DATE 10/23/07  
INV. NO. 2008060660

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 22 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: -097.11972.37.65293, PERFS 2332'-2334'

Plugged through: TBG

District: 02

Signed

*Duane Krueger*

(TECHNICIAN)

PKT