

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-01380-00-00
Spot: E2NWNW Sec/Twnshp/Rge: 4-20S-2W
4511 feet from S Section Line, 4235 feet from E Section Line
Lease Name: STUCKY Well #: 2
County: MCPHERSON Total Vertical Depth: 3401 feet

Operator License No.: 32778
Op Name: CAT ENERGY, LLC
Address: PO BOX 507
GALVA, KS 67443

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3399	520	135 SX
SURF	8.625	155		90 SX

110.53

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/12/2007 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3,345' & TOP WITH 5 SXS. CEMENT. RIP 5 1/2" CASING & PULL. RUN TUBING TO 475' & SPOT 35 SXS. CEMENT. PULL TUBING TO 250' & CIRCULATE CEMENT TO THE SURFACE.

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 10/12/2007 11:30 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

HOLE BRIDGED OFF @ 3,300'. SANDED TO 3,280' & TOPPED WITH 5 SXS. CEMENT. RIPPED 5 1/2" CASING @ 520' & PULLED. RAN 2 3/8" TUBING TO 504' & SPOTTED 35 SXS. CEMENT. PULLED TUBING TO 282' & CIRCULATED 225 SXS. CEMENT TO SURFACE. CHECKED TOP PLUG ON 10/16/2007 - CEMENT @ SURFACE.

Perfs:

INVOICED
DATE 10/23/07
INV. NO. 2008060662

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 22 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENT. INVOICE #32597.

Plugged through: TBG

District: 02

Signed Michael R Wilson
(TECHNICIAN)