

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-079-20622-00-01  
Spot: N2SENE Sec/Twnshp/Rge: 21-22S-3W  
3652 feet from S Section Line, 573 feet from E Section Line  
Lease Name: EDIGER A Well #: 1  
County: HARVEY Total Vertical Depth: 3830 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 1321 W 93 N PO BOX 360  
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3826	2014	150 SX
SURF	8.625	278		175 SX

124.48

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/15/2007 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 3,645' & TOP WITH 5 SXS. CEMENT. RIP 5 1/2" CASING. PULL 5 1/2" CASING. PULL CASING TO 525' SPOT 35 SXS CEMENT. PULL 5 1/2" CASING TO 325' & CIRCULATE CEMENT TO THE SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/15/2007 12:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

SAND TO 3,130' & TOPPED WITH 5 SXS. CEMENT. RIPPED 5 1/2" CASING @ 2,014'. PULLED 5 1/2" CASING TO 544'. CIRCULATED 60 BBLs. WATER WITH 21 SXS. BENTONITE TO THE SURFACE. SPOTTED 35 SXS. CEMENT WITH 100 LBS. HULLS @ 544'. PULLED 5 1/2" CASING TO 341' & CIRCULATED 160 SXS. CEMENT WITH 300 LBS. HULLS TO THE SURFACE. CHECKED TOP PLUG ON 10/16/2007 - CEMENT @ SURFACE.

Perfs:

Top	Bot	Thru	Comments
3704	3712		
3698	3700		

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 22 2007

CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
DATE 10/23/07  
INV. NO. 2008060663

Remarks: USED 60/40 POSMIX W/4% GEL, 21 SXS BENTONITE, & 400 LBS HULLS BY COPELAND ACID & CEMENT. INVOICE #32159.

Plugged through: CSG

District: 02

Signed Michael R. Wilson  
(TECHNICIAN)

PKT