

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-29086-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 29-23S-19E  
660 feet from S Section Line, 330 feet from W Section Line  
Lease Name: HOWARD Well #: 29-14  
County: ALLEN Total Vertical Depth: 1205 feet

Operator License No.: 33428  
Op Name: FORT SCOTT METHANE PARTNERS, L  
Address: 2329 W MAIN ST # 301  
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1179	0	150sx
SURF	8.625	21	0	4sx

39.16

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/16/2007 10:00 AM  
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 1179' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE CASING HAD NOT BEEN PERFORATED. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 4 1/2" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE  
Date/Time Plugging Completed: 10/16/2007 10:45 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

SPOOLED PLASTIC TUBING WAS RAN INTO THE WELL TO T.D.. CEMENT WAS PUMPED INTO THE TUBING UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING AT SURFACE. THE TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 96 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

RECEIVED  
KCC DISTRICT #3

OCT 17 2007 CPT

CHANUTE, KS

INVOICED  
DATE 10/23/07  
INV. NO. 2008060664

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 22 2007

CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

PCT