

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23142-00-00
Spot: NWNW Sec/Twnshp/Rge: 22-27S-22E
660 feet from N Section Line, 600 feet from W Section Line
Lease Name: KELLER Well #: 22-11
County: BOURBON Total Vertical Depth: 742 feet

Operator License No.: 33428
Op Name: FORT SCOTT METHANE PARTNERS, L
Address: 2329 W MAIN ST # 301
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	728	0	80 SX CMT.
RBP		580		
SURF	8.625	22	0	4 SX CMT. 35.00

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/03/2007 1:00 PM
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 728' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 10/03/2007 2:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE MIXED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 700 PSI. 60 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
655	661		
648	650		
611	613		
591	593		
409	411		
282	284		
268	271		
256	259		

RECEIVED
KCC DISTRICT #3

OCT 17 2007 CPT

CHANUTE, KS

INVOICED

DATE 10/23/07

INV. NO. 2008060664

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 22 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: CSG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PKT