

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-00305-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 19-19S-5W
319 feet from S Section Line, 2325 feet from E Section Line
Lease Name: MYERS Well #: 1
County: MCPHERSON Total Vertical Depth: 3944 feet

Operator License No.: 7775
Op Name: WILTON PETROLEUM, INC.
Address: PO BOX 391
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3490	<u>1270</u>	100 SX CMT
SURF	8	186	<u>KCC PMT</u>	125 SX CMT

128.18

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2007 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRYE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: GREG EVES Witness Type: NONE
Date/Time Plugging Completed: 10/05/2007 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 3370' AND CAP WITH 5 SX'S CEMENT, CUT OFF CASING @ 1270' AND PULL TO 800' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS, PULL CASING TO 430' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS, PULL CASING TO 250' AND CIRCULATE CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3420	3430		MISS

INVOICED

DATE 10/23/07
INV. NO. 2008060670

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 22 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 45 GEL. QUALITY TICKET #1611. USED 170 SX'S.

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

PKP