

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20083-00-00
Spot: SESWNW Sec/Twnshp/Rge: 27-2S-14E
2993 feet from S Section Line, 4383 feet from E Section Line
Lease Name: BAUMAN A Well #: 1
County: NEMAHA Total Vertical Depth: 3903 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3884		
SURF	8.625	252		

126.85

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/05/2007 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KEVIN WILSON Company: LARSON ENGINEERING, INC. Phone: (620) 653-7368

Proposed Plugging Method: 50 SACKS OF CEMENT AT BOTTOM, 50 SACKS OF CEMENT AT 1000', AND CIRCULATE CEMENT FROM 300' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/05/2007 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

PERFORATED THE 5 1/2" PRODUCTION CASING AT 1000' AND 300'. RAN THE TUBING DOWN TO 2250' AND PUMPED 50 SACKS OF CEMENT. PULLED THE TUBING UP TO 1000' AND CIRCULATED 50 SACKS OF CEMENT THROUGH THE 5 1/2" CASING. PULLED THE TUBING UP TO 300' AND CIRCULATED 100 SACKS OF CEMENT FROM 300' TO SURFACE.

RECEIVED
KCC DISTRICT #3

SEP 13 2007 TCH

CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
3566	3569		

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Horman
(TECHNICIAN)

INVOICED
DATE 10/15/07
INV. NO. 2008 060576

PH