

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-21382-00-00  
Spot: NWNE Sec/Twnshp/Rge: 12-19S-24W  
4620 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: OBEE Well #: 1  
County: NESS Total Vertical Depth: 4306 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4250		
CIBP		4260		
PROD 5.5		4297	0	
SURF	8.625	327		WITH 250 SX CMT

139.95

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/10/2007 8:20 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING Phone: (316) 267-3241

Proposed Plugging Method: PUMP 45 SX CMT & 200# HULLS. PRESSURE TEST. PERFORATE AND CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/10/2007 11:30 AM KCC Agent: MICHAEL MAIER

**Actual Plugging Report:**

PUMPED 45 SX CMT & 200# HULLS. MAXIMUM PRESSURE 600#. PERFORATE AT 850'. PUMPED 160 SX CMT. DID NOT GET CIRCULATION FROM BACKSIDE. SHUT IN & PUMP 25 SX CMT DOWN BACKSIDE. PRESSURED TO 400# & HELD.

**Perfs:**

Top	Bot	Thru	Comments
4297	4306	OH	
4211	4214		


INVOICED

DATE 10/15/07  
INV. NO. 2008060580

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01



Signed Michael Maier

(TECHNICIAN) RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 09 2007

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS

*Handwritten initials/signature*