

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6 030852

JAN 23 1987
API NUMBER 15-163-22,910-00-00

150/s
E/2 N/4 SEC. 25, T 10 S, R 19 W

1830 feet from S section line
4140 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5533

Lease Name DALWE Well # 4

Operator: ARROWHEAD PET. INC.

County ROOKS 113.10

Name & Address P.O. Box 8287 MUNGER STATION

Well Total Depth 3480' feet

WICHITA, KANSAS
67216

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 232'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor BIG SPRINGS DRIG, INC. License Number 5381

Address Box 8287 MUNGER STATION WICHITA, KS

Company to plug at: Hour: AM Day: 23 Month: 1 Year: 19 87

Plugging proposal received from TERRY AUSTIN

(company name) BIG SPRINGS DRIG. (phone) _____

were: 8 5/8 SET @ 232' CWC. CIRC. HOLE W/ NO LESS THAN 36 VLS. MUD,
FROM BOTTOM. WITH NO LOSS OR GRAINDE FLUID SPOT CNT. PLUGS
W/ D.P. BALLANCE ALL PLUGS W/ MUD ORDER 190 SX. 60/40 P02 67 GEL
3% ca - 8 5/8 W.P. ALLIED CNT. CO.

Plugging Proposal Received by Carl Goodnow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:15 AM Day: 23 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT SPOT D.P. @ 1350' DISPLACE 25 SX. CNT. MIX

LAYDOWN D.P. TO 800' DISPLACE 100 SX. CNT. MIX + 1 SX. HULLS

LAYDOWN D.P. TO 270' DISPLACE 40 SX. CNT. MIX LAYDOWN

D.P. ADJUST MUD IN HOLE TO KELLY DEPTH (40') PUSH W.P.

TO KELLY DEPTH (40') ± FILL HOLE TO BASE OF CELLAR W/ 10 SX. CNT. MIX.

CIRCULATE 15 SX. CNT. MIX. IN RATHOLE W/ JOINT OF PIPE. Plug COMPLETE.

Remarks: ELEV 2117 ANHY 1338' - 68'

(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 2-2-87

Signed Carl Goodnow (TECHNICIAN)

INV. NO. 16039

STATE CORPORATION COMMISSION
01-30-1987
JAN 30 1987
CONSERVATION DIVISION
Wichita, Kansas