

12-28

13  
R

4-071025

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-163-20,904-00-00

NW NE NW /4 SEC. 31, 10 S, 19 W  
4950 feet from S section line  
3630 feet from E section line

RECEIVED  
KANSAS CORPORATION COMMISSION

Operator license# 5252

Lease Keller well # 1

Operator: R.P. Nixon

County Rooks

Address: 207 West 12th Street  
Hays, Kansas 67601  
Paul Nixon

Well total depth 3765 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 253 feet

JAN 12 1993  
01-12-1993  
CONSERVATION DIVISION  
WICHITA, KS

12.36

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Allied Cementing License#     

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 28 Month: December Year: 92

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon Company Phone: 913-628-3834

Were: 8 5/8" - 253' S.P. cwc. w/150 sx. cement. 4 1/2" casing set @ 3764' w/125 sx. cement. Elv. 2208' - Anhy. 1612'. 4 1/2" casing squeezed @ 1053' to 1063' w/250 sx. cement. Proposal order 300 sx. 65/35 pozmix 8% gel and 5 sx. hulls. Perf. 4 1/2" casing @ 1620' pump cement. In with pump truck - load both 4 1/2" casing and 4 1/2" x 8 5/8" annulus with cement. Shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt  
Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 2:45P.M., Day: 28, Month: December, Year: 92

Actual plugging report: Nixon order 300 sx. 65/35 pozmix - 8% gel. and 5 sx. hulls. Pumped in 4 1/2" casing and 4 1/2" x 8 5/8" casing with pump truck. 1) Pumped 100 sx. cement with 3 sx. hulls in 4 1/2" casing and displaced cement. 2) Perferated 4 1/2" casing @ 1620'. 3) Pumped in 4 1/2" casing w/150 sx. cement w/2 sx. hulls. Max. pressure 150 P.S.I. 4) Squeezed 4 1/2" x 8 5/8" annulus w/50 sx. cement. Max. pressure 500 P.S.I. Shut in @ 150 P.S.I.

Remarks: By: Allied Cement  
Condition of casing(in hole): GOOD X BAD      Anhy.plug: YES X NO       
Bottom plug(in place): YES X, CALC     , NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING X. Elevation: 2208 GL     

I did [X] / did not [ ] observe the plugging.

*Marion J. Schmidt*  
(agent)

INVOICED  
DATE 1-25-93  
REV. NO. 37235