

4-25

6 031370

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-23,091-00-0
NE NE SW, SEC. 33, T 10 S, R 19 W X E X

2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 03091

Lease Name Palmberg Well # 1

Operator: Co-Kan Resources

County Rooks 120.28

Name & Address: Box 854

Well Total Depth 3701 feet

Address: Hays, Ks. 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Oper License Number 8241

Address Russell, Ks.

Company to plug at: Hour: AM Day: 25 Month: April Year: 19 90

Plugging proposal received from Emphasis

(company name) Emphasis (phone)

were: 8 5/8" set at 249' w/145 sks. Circ hole w/no less than 36 vis mud with no loss or gain in fluid. Balance plugs w/mud. Order 215 sks 60/40 poz 6% gel 3% cc.

Allied Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN) x

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00AM Day: 25 Month: April Year: 19 90

ACTUAL PLUGGING REPORT Spot plugs with drill pipe at arb w/25 sks

1200' w/25 sks

800' w/100 sks hulls

300' w/40sks

40' w/10 sks wiper plug.

15 sks in ratthole w/joint of pipe.

Remarks: Anhy 1184 - 1525. Elev. 2123 KB

(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE 6-27-90

INV. NO. 28495

Sub. S.

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS
JUN 20 1990