

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-00337-00-01
Spot: SWSWSW Sec/Twnshp/Rge: 35-24S-2E
329 feet from S Section Line, 4992 feet from E Section Line
Lease Name: EILERT Well #: 1 INP
County: HARVEY Total Vertical Depth: 2852 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2850		
SURF	8.625	169		

9269

Well Type: EOR UIC Docket No: E25123.1 Date/Time to Plug: 09/18/2000 7:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ED NEMNICH/JOE STRUBE Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Sand to 2,790' & top with 5 sxs. cement. 8 5/8" X 5 1/2" annulus cemented from 200' to surface for Alt 1 requirements.
Run tubing inside 5 1/2" casing to 300' & circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/18/2007 11:00 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Sanded to 2,790' & topped with 5 sxs. cement. Checked 8 5/8" X 5 1/2" annulus - cement at surface. Perforated 5 1/2" casing @ 300'. Ran 2 3/8" tubing to 300' & circulated 60 sxs. cement to the surface.

INVOICED
DATE 10/18/07
INV. NO. 2008060627

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 16 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENT. INVOICE # 32197.

Plugged through: TBG

District: 02

Signed Michael Wilson
(TECHNICIAN)