

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-00339-00-00
Spot: SESWSW Sec/Twnshp/Rge: 35-24S-2E
339 feet from S Section Line, 4473 feet from E Section Line
Lease Name: EILERT A Well #: 3
County: HARVEY Total Vertical Depth: 2851 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2850		
SURF	8.625	145		

92-66

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/18/2007 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ED NEMNICH / JOE STRUB Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Sand to 2,790' & top with 5 sxs. cement. Circulate cement from 250' to surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL
Date/Time Plugging Completed: 09/18/2007 2:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Sanded to 2,790' & topped with 5 sxs. cement. Perforated 5 1/2" casing @ 250'. 8 5/8" X 5 1/2" annulus cemented to 35' - filled with 40 sxs. cement. Ran 2 3/8" tubing to 270' & circulated 60 sxs. cement to the surface.

INVOICED

DATE

10/18/07

INV. NO.

2008060627

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 16 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENT. INVOICE #32198.

Plugged through: TBG

District: 02

Signed

Michael R Wilson

(TECHNICIAN)

PLG