

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-079-00342-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 35-24S-2E  
1068 feet from S Section Line, 4350 feet from E Section Line  
Lease Name: EILERT Well #: 5  
County: HARVEY Total Vertical Depth: 2900 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH ST  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2900		
SURF	8.625	200		165 SX <u>94.25</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/19/2007 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: ED NEMNICH / JOE STRUB Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Sand to 2,790' & top with 4 sxs. cement. Circulate cement form 250' to the surface.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/19/2007 10:00 AM KCC Agent: DAVE WERTZ

Actual Plugging Report:

Perfs:

Sanded to 2,790' & topped with 4 sxs. cement. Perforated 5 1/2" casing @ 250'. Ran 1" tubing down 8 5/8" X 4 1/2" annulus to 270' & circulated 135 sxs. cement to the surface inside 5 1/2" casing & in annulus.

INVOICED  
DATE 10/18/07  
INV. NO. 2008060627

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 16 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENT. INVOICE # 32199.

Plugged through: TBG

District: 02

Signed Don Wertz  
(TECHNICIAN)

PKT