

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-20892-00-00
Spot: S2SESW Sec/Twnshp/Rge: 28-18S-6E
357 feet from S Section Line, 3247 feet from E Section Line
Lease Name: METHVIN Well #: 2
County: CHASE Total Vertical Depth: 2107 feet

Operator License No.: 5192
Op Name: SHAWMAR OIL & GAS CO., INC.
Address: 1116 E MAIN PO BOX 9
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2095		150/200 SX CMT.
SURF	8.625	200		125 SX CMT.

608 48

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/04/2007 8:00 AM
Plug Co. License No.: 33307 Plug Co. Name: FLINT HILLS OIL CO., LLC
Proposal Rcvd. from: BENNY KEY Company: SHAWMAR OIL & GAS CO., INC. Phone: (620) 382-2932

Proposed Plugging Method: Bridge plug @ 1,650'. Run tubing to 1,650'. Spot 4 sxs. cement on top of B.P. Pull tubing to 1,543' & spot 20 sxs. cement. Pull tubing to 608' & spot 20 sxs. cement. Pull tubing to 250' & circulate cement to surface.

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/04/2007 2:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Ran 2 3/8" tubing to 1,640' & circulated water to surface. Spotted 30 sxs. cement @ 1,640'. Pulled tubing to 607' & circulated 55 sxs. cement to the surface.

Perfs:

Top	Bot	Thru	Comments
2077	2081		
2038	2044		
1543	1546		
608	610		

INVOICED
DATE 10/18/07
INV. NO. 2008060628

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 16 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY CONSOLIDATED OILWELL SERVICES, INC. INVOICE #12724.

Plugged through: TBG

District: 02

Signed Michael R Wilson
(TECHNICIAN)

PAT