

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-20389-00-01  
Spot: SWNE Sec/Twnshp/Rge: 21-33S-4W  
3279 feet from S Section Line, 1790 feet from E Section Line  
Lease Name: SPRINGER OWWO Well #: 1  
County: SUMNER Total Vertical Depth: 4370 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4303	<u>3390</u>	150 SX
SURF	8.625	258		

KCC Pkt per operator 142-03

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/08/2007 2:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MILE'S TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK PERFS TO 4120' AND CAP WITH 4 SKS OF CMT. REC PIPE. 35 SKS 800'. 35 SKS 500', CIRC 310-0

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/09/2007 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

-97.75320,37.16335. THE PERFS WERE COVERED WITH SAND TO 4120' AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 3390' AND PULLED TO 2200', WHERE THE WELL KICKED OFF. SPOTTED 100 SKS OF CMT. PULLED PIPE TO 800' WHERE 35 SKS OF CMT WAS SPOTTED. PULLED PIPE TO 500', WHERE CMT WAS CIRC TO SURFACE. CHECKED CMT ON 8-9-2007, CMT FELL TO 125 FEET AND STILL GIVING UP SMALL AMOUNT OF GAS. CALLED FOR CMT AND RAN 125' OF POLY PIPE. TIED ON AND CIRCULATED HOLE FULL OF CMT. GAS PRESSURE WORSE AFTER ADDITIONAL CMTNG. COULD NOT SQUEEZE BECAUSE OF BAD THREADS ON 8.625. DECIDED TO WASH OUT CMT AND DRILL OUT 500' PLUG AND 800' PLUG AND CIRCULATE WELL WITH DRILLING MUD AND REPLUG WELL. 8-24-2007, THE CEMENT WAS DRILLED OUT TO 1835', WHERE THE GAS WAS KILLED WITH DRILLING MUD. WE DECIDED TO SPOT A 50 SKS CMT PLUG AT 1835'. THE GAS REMAINED DEAD. PULLED TUBING TO 854', WHERE 50 SKS OF CMT WAS SPOTTED. PULLED TO TUBING TO 509', WHERE 50 SKS OF CMT WAS SPOTTED. PULLED TUBING TO 305', WHERE CMT WAS CIRCULATED TO SURFACE. RECHECK PLUGS ON 8-27-2007, AND FOUND THE CMT REMAINED FULL. WELL PLUGGED. PROBABLY WHITE CLOUD GAS

Perfs:

Top	Bot	Thru	Comments
4178	4190		MISS

**INVOICED**  
DATE 10/18/07  
INV. NO. 2008060629


RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 16 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND ACID AND CMT COMMON

Plugged through: TBG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

