

Operator Name: Kutter Oil Co., Inc. Lease Name: Jackson Well #: 5*
 Sec. 1 Twp. S. R. East West County: Greenwood

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No
 (Submit Copy)

List All E. Logs Run:

Log Formation (Top), Depth and Datum Sample

Name: Bartlesville Top: 2316 Datum: -1114

CASING RECORD New Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacjs Used	Type and Perce Additives
Surface	12 1/4	8 5/8	23	210	Class A	105	3% CC
Prod.	7/7/8	5 1/2	14	2365	Thick Set C	100	

ADDITIONAL CEMENTING / SQUEEZE RECORD

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

PERFORATION RECORD - Bridge Plugs Set/Type
Specify Footage of Each Interval Perforated

Shots Per Foot	Perforation Interval	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
2	Perf 2321' to 2331'	500 Gal FE Acid	

TUBING RECORD

Size: <u>2 3/8</u>	Set At: <u>2346</u>	Packer At:	Liner Run: <input type="checkbox"/> Yes <input type="checkbox"/> No
--------------------	---------------------	------------	---

Date of First Resumerd Production, SWD or Enhr. _____ Producing Method

Flowing Pumping Gas Lift Other (Explain)

Estimated Production Per 24 Hours	Oil Bbls. <u>N/A</u>	Gas Mct	Water Bbls.	Gas-Oil Ratio	Gravity
-----------------------------------	----------------------	---------	-------------	---------------	---------

Disposition of Gas Vented Sold Used on Lease
 (If vented, Sumit ACO-18.)

METHOD OF COMPLETION

Open Hole Perf. Dually Comp. Commingled

Other (Specify) _____

Production Interval

**BLUE STAR
ACID SERVICE, INC.**

PO Box 103
Eureka, Kansas 67045

Cementing Ticket
and Invoice Number

ORIGINAL
No. 5172

Date 12-1-03	Customer Order No.	Sect. 1	Twp. 25S	Range 8E	Truck Called Out 2:30 AM	On Location 3:30 AM	Job Began 4:00 AM	Job Completed 4:30 AM
Owner Kutter Oil, Inc.		Contractor C & G Drig.			Charge To Kutter Oil, Inc.			
Mailing Address 303 S. High		City EUREKA			State KS 67045			
Well No. & Form HAP JACKSON # 5		Place			County Greenwood		State KS	
Depth of Well 210'	Depth of Job 211'	Casing (New) Used	Size 8 5/8	Weight 23 #	Size of Hole Amt. and Kind of Cement 12 1/4 105 SKS	Cement Left in casing by	(Request) Necessity 15' feet	
Kind of Job SURFACE					Drillpipe	(Rotary) Cable	Truck No. # 21	

Price Reference No.	# 1
Price of Job	425.00
Second Stage	
Mileage 15.7	33.75
Other Charges	
Total Charges	458.75

Remarks: SAFETY Meeting! Rig up to 8 5/8 CASING. BREAK Circulation with 10 BBL fresh water. Mixed 105 SKS Regular Cement with 3% CaCl2 1/4" floccle per/sk. Displace with 12.5 BBL fresh water. SHUT CASING IN. Good Cement Returns to SURFACE = 6 BBL STURR. Job Complete. Rig down.

Cementer KEVIN MCCOY
 Helper MIKE, JUSTIN District EUREKA State KS
 The above job was done under supervision of the owner, operator, or his agent whose signature appears below.
THANK YOU Called By Tim
 Agent of contractor or operator

Sales Ticket for Materials Only

Quantity Sacks	BRAND AND TYPE	PRICE	TOTAL
105 SKS	Regular Class "A" Cement	7.75	813.75
296 #	CaCl2 3%	.35	103.60
25 #	Floccle 1/4" per/sk	1.00	25.00
RECEIVED			
APR 06 2004			
KCC WICHITA			
Plugs	105 SKS Handling & Dumping	.50	52.50
	4.93 TONS Mileage 15	.80	59.16
	Sub Total		1512.76
	Delivered by Truck No. # 16	Discount	
	Delivered from EUREKA	Sales Tax	6.3% 95.30
	Signature of operator <u>Kevin McCoy</u>	Total	1,608.06

**BLUE STAR
ACID SERVICE, INC.**

PO Box 103
Eureka, Kansas 67045

Cementing Ticket
and Invoice Number

ORIGINAL
No. 5213

Date 12-4-03	Customer Order No.	Sect. 1	Twp. 25 S	Range 8 E	Truck Called Out 7:00 AM	On Location 10:30 AM	Job Began 11:50 AM	Job Completed 12:30 PM
Owner Kutter Oil Inc.		Contractor C + G Drig			Charge To Kutter Oil Inc.			
Mailing Address 303 S. High		City Eureka			State KS 67045			
Well No. & Form HAP JACKSON # 5		Place Greenwood			State KS			
Depth of Well 2365	Depth of Job 2370	Casing (New) Size 5 1/2 (Used) Weight #14	Size of Hole Amt. and Kind of Cement 7 1/8 100 T.S.		Cement Left in casing by	Request Necessity 0 feet		
Kind of Job Longstring		Drillpipe	Tubing		Rotary Cable		Truck No. # 25	

Price Reference No. #1
Price of Job 665.00
Second Stage
Mileage 157 33.75
Other Charges
Total Charges 698.75

Remarks Safety Meeting, Rig up to 5 1/2 casing, Break circulation w/ 25 Bbl Fresh water, Mix 100 SKs Thick set cement w/ 4 lb Kol Seal Per/SK. SHUT Down, Release Plug, Displace w/ 58 Bbl water. Final Pump PST 500 # Bump Plug to 1000 # check float float held. GOOD circulation During cementing Procedure. Close casing IN AT 0 PSI.
NOTE. Mix cement w/ city water
" Rotate casing while displacing cement
" Displace cement at 7 Bbl per/min
Slow to 4 Bbl at Tail End of Job.

Cementer Russell McCoy

Helper Rick - Troy - Jason

District Eureka

State KS

The above job was done under supervision of the owner, operator, or his agent whose signature appears below.

THANK YOU

called by Tim Gulick

Agent of contractor or operator

Sales Ticket for Materials Only

Quantity Sacks	BRAND AND TYPE	PRICE	TOTAL
100	SKs Thick set cement	10.75	1075.00
400 #	Kol - Seal 4 # Per/SK	.30	120.00
RECEIVED APR 06 2004 KCC WICHITA			
1	5 1/2 A.F.U. INSERT FLOAT SHOE	160.00	160.00
1	5 1/2 TOP Rubber Plug	40.00	40.00
Plugs	100 SKs Handling & Dumping	.50	50.00
	5.5 Ton Mileage 15	.80	66.00
	Delivered by Truck No.	Sub Total	2,209.75
	Delivered from Eureka	Discount	
	Signature of operator Russell McCoy	Sales Tax 6.3 %	139.21
		Total	2,348.96