

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-011-22999-00-00  
Spot: NENENW Sec/Twnshp/Rge: 14-27S-22E  
330 feet from N Section Line, 2310 feet from W Section Line  
Lease Name: OBRIEN CATTLE CO Well #: 14-21  
County: BOURBON Total Vertical Depth: 705 feet

Operator License No.: 33428  
Op Name: FORT SCOTT METHANE PARTNERS, L  
Address: 2329 W MAIN ST # 301  
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	696	0	80sx
SURF	8.625	20	0	4sx

\$ 35

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/04/2007 10:00 AM  
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 696' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/04/2007 11:30 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS SHUT IN AT 400 PSI. 66 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

RECEIVED  
KCC DISTRICT #3

OCT 8 2007 CPT

CHANUTE, KS

INVOICED  
DATE 10/18/07  
INV. NO. 2008060606

Remarks: SPOT LOCATION ESTABLISHED VIA GPS AS OBR14-21 AT 37.70254 N & 094.97150 W.

Plugged through: CSG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN) RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 15 2007

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS

PCT