

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23103-00-00
Spot: NENENW Sec/Twnshp/Rge: 9-27S-22E
350 feet from N Section Line, 2300 feet from W Section Line
Lease Name: KELLER Well #: 9-21
County: BOURBON Total Vertical Depth: 864 feet

Operator License No.: 33428
Op Name: FORT SCOTT METHANE PARTNERS, L
Address: 2329 W MAIN ST # 301
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	858	0	
SURF	8.625	21	0	
T1	2.375	848	848	

35

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 10/04/2007 3:00 PM
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 858' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 10/04/2007 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 300 PSI.

Perfs:

Top	Bot	Thru	Comments
791	794		
751	753		
632	634		
600	602		
420			
406	409		
395	398		

RECEIVED
KCC DISTRICT #3

OCT 10 2007

CHANUTE, KS

CPT

INVOICED
DATE 10/18/07
INV. NO. 2008060604

Remarks:

Plugged through: CSG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 15 2007

CONSERVATION DIVISION
WICHITA, KS

PT