

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-011-23104-00-00  
Spot: NWSESENW Sec/Twnshp/Rge: 11-27S-22E  
2200 feet from N Section Line, 2140 feet from W Section Line  
Lease Name: KELLER Well #: 11-22  
County: BOURBON Total Vertical Depth: 737 feet

Operator License No.: 33428  
Op Name: FORT SCOTT METHANE PARTNERS, L  
Address: 2329 W MAIN ST # 301  
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	734	0	
SURF	8.625	20	0	
T1	2.375	674	674	\$35-

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/04/2007 11:30 AM  
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: MIKE KEPLEY Company: KEPLEY WELL SERVICE, A GENER Phone: (620) 431-9212

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 734' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 4 1/2" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/04/2007 12:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 600 PSI. 78 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
652	656		
646	649		
596	598		
580			
460	462		
408	410		
277	280		
269	271		
257	260		

RECEIVED  
KCC DISTRICT #3

OCT 10 2007 CPT

CHANUTE, KS


INVOICED  
DATE 10/18/07  
INV. NO. 2008060606

Remarks: SPOT LOCATION ESTABLISHED VIA GPS AS 094.97195 W & 37.71212 N.

Plugged through: CSG

District: 03

Signed



(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

OCT 15 2007

CONSERVATION DIVISION  
WICHITA, KS

