

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-27194-00-00  
Spot: SENE SW Sec/Twnshp/Rge: 7-24S-14E  
1875 feet from S Section Line, 2470 feet from W Section Line  
Lease Name: DYE Well #: 41  
County: WOODSON Total Vertical Depth: 1755 feet

Operator License No.: 33640  
Op Name: HAAS PETROLEUM, LLC  
Address: 800 W 47TH ST STE # 409  
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.25	40	0	

57.04

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/05/2007 12:00 PM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: MARK HAAS Company: HAAS PET. Phone: (913) 851-9845

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASD BORE TO 1755'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 907', AND TO PLACE A CONTINUOUS CEMENT PLUG FROM 240' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/05/2007 12:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

DRILL PIPE WAS RAN INTO THE WELL TO T.D.. 15 SACKS OF CEMENT WERE PUMPED THROUGH THE DRILL PIPE TO T.D.. THE PIPE WAS PULLED TO 907' AND 15 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE DRILL PIPE WAS PULLED TO 240'. CEMENT WAS PUMPED INTO THE DRILL PIPE UNTIL CEMENT CIRCULATED FROM THE SURFCE CASING AT SURFACE. THE DRILL PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

INVOICED  
DATE 10/18/07  
INV. NO. 2008060607

RECEIVED  
KCC DISTRICT #3

OCT 8 2007 OPT

CHANUTE, KS

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 15 2007

CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

PET