

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-27252-00-00  
Spot: W2W2E2W2 Sec/Twnshp/Rge: 30-25S-14E  
2640 feet from N Section Line, 1480 feet from W Section Line  
Lease Name: NORDMEYER Well #: 25-07  
County: WOODSON Total Vertical Depth: 1337 feet

Operator License No.: 30345  
Op Name: PIQUA PETRO, INC.  
Address: 1331 XYLAN RD  
PIQUA, KS 66761

43.45

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/27/2007 10:00 PM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: ADAM SPLECTER Company: PIQUA PETRO, INC. Phone: (620) 468-2681

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED BORE TO 1337. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 800'. AND TO PLACE A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE  
Date/Time Plugging Completed: 08/28/2007 12:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

DRILL PIPE WAS RAN INTO THE WELL BORE TO T.D.. 15 SACKS OF CEMENT WERE PUMPED THROUGH THE DRILL PIPE TO T.D.. THE DRILL PIPE WAS PULLED TO 800' AND 15 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE DRILL PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE DRILL PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE DRILL PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED  
KCC DISTRICT #3  
OCT 8 2007 CPT  
CHANUTE, KS

INVOICED  
DATE 10/18/07  
INV. NO. 2008060666

Remarks:

Plugged through: TBG

District: 03

Signed

*Clayton P. Titel*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

OCT 15 2007

CONSERVATION DIVISION  
WICHITA, KS

*PVT*