

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21315-00-00
Spot: SWSENE Sec/Twnshp/Rge: 13-20S-16W
3003 feet from S Section Line, 1106 feet from E Section Line
Lease Name: OLIVER SMITH SWD Well #: 3-13
County: PAWNEE Total Vertical Depth: 4000 feet

KCC
PLUG
PER
OPEN
10/17

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3882	2070	WITH 125 SX CMT
SURF	8.625	1085		WITH 400 SX CMT

130.00

Well Type: SWD UIC Docket No: D25931.0 Date/Time to Plug: 10/02/2007 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/02/2007 1:20 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3830' & 5 SX CMT. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1110' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3882	4000	OH	

INVOICED
DATE 10/18/07
INV. NO. 2008060620

Remarks: USED 60/40 POZMIX 4% GEL BY QULAITY CEMENTING

Plugged through: CSG

District: 01



Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

OCT 15 2007

CONSERVATION DIVISION
WICHITA, KS