

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-21946-00-00  
Spot: SESESW Sec/Twnshp/Rge: 35-15S-21W  
330 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: RASE B Well #: 1  
County: TREGO Total Vertical Depth: 4300 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4299	0	155 SX
SURF	8.625	355	0	250 SX

**\$ 139.75**

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/17/2007 12:30 PM  
Plug Co. License No.: 33369 Plug Co. Name: XTREME WELL SERVICE, INC.  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (316) 772-8649

Proposed Plugging Method: Ordered 265 sxs 60/40 pozmix - 4% gel - 600# hulls - 1 bag cc.  
DV Tool at 1650' w/500 sxs cement to surface.  
PBTB 4260'. Squeeze casing leaks at 3439'-3467' w/200 sxs.  
Fluid level 2200'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/17/2007 4:30 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

RIH to 4200'. Rigged to tubing - pumped 40 sxs 60/40 pozmix - 4% gel - 3% cc with 200# hulls mixed in.  
Pulled tubing to 3750'. Rigged to tubing - pumped 22 sxs gel with 200# hulls mixed in - pumped 10 sxs 60/40 pozmix to clear gel.  
Pulled tubing to 1700'. Rigged to tubing - pumped 150 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate cement to surface.  
Pulled tubing - rigged to 5 1/2" casing with a swedge - pumped 15 sxs cement.  
Max. P.S.I. 450#. S.I.P. 450#.  
Dug out backside of 8 5/8" - pulled bull plugs - backside full of cement.

**Perfs:**

Top	Bot	Thru	Comments
4181	4184		

INVOICED

DATE 10/22/07  
INV. NO. 2008060648

Remarks: ALLIED CEMENTING COMPANY-TICKET #35771.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)


RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

OCT 19 2007

CONSERVATION DIVISION  
WICHITA, KS

OCT 18 2007

STATE KANS COUNTY TREGO RE-ISSUE 35-15S-21W  
 FIELD RASE-1/4 MI W PROD (MARMATON) SE SE SW  
 OPER BEREXCO INC 330FSL 2970FEL SEC  
 WELL 1 RASE "B" WELL CLASS WOE  
 API 15-195-21946-0000 STATUS OIL  
 SPUD 01/11/1988 COMP 02/19/1988  
 DTD 4300 LTD FTD MARMATON PBTD



Petroleum Information

LOC 19 MI SE TREGO CENTER, KS

IP IPP 4 BOPD 170 BW GTY 40 NATURAL  
 PROD ZONE: PAWNEE 4181-4184  
 (PAWNEE EXTENSION)

EL: 2330 KB 2325 GR
LOG TOPS:
HEEBNER 3712 -1382
TORONTO 3734 -1404
LSG-KANSAS CITY 3754 -1424
MARMATON 4048 -1718
PAWNEE 4097 -1767
TD 4300 -1970

CSGS: 8 5/8 @ 355 W/ 250 SACKS  
 5 1/2 @ 4299 W/ 155 SACKS  
 DV TOOL @ 1650 W/500 SX  
 TBGS: 2 3/8 @ 4125  
 DRLG COMP 1/18/88 RIG REL 1/18/88  
 DSTS: DST 1 4146-4186 PAWNEE REC 186 FT GOCM 559 FT GMWO  
 INIT OP 15M IFP 191 FFP 321 ONE OP  
 DST 2 4198-4210 PAWNEE REC 185 FT MUD 290 FT SWTR  
 INIT OP 15M IFP 840 FFP 979 ONE OP  
 DST 3 4226-4248 PAWNEE REC 60 FT MUD 1425 FT SWTR  
 INIT OP 15M IFP 368 FFP 612 ONE OP  
 PERFS: PAWNEE PERF 4181-4184: DID NOT TREAT NO CORES  
 CONTR: BEREDCO INC GEOL: P SAM HOUSTON  
 REISSUE TO: CORRECT FORM @ TD, ADD DSTS, LOG TOPS, PROD CSG, TBG, PERFS, IP  
 REPLACEMENT FOR CARD ISSUED 5/10/88

KS R6-102390