

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23471-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 24-21S-14W
330 feet from S Section Line, 2455 feet from E Section Line
Lease Name: BENNETT TRUST Well #: 24-1
County: STAFFORD Total Vertical Depth: 3751 feet

Operator License No.: 32639
Op Name: CORAL PRODUCTION CORPORATION
Address: 1600 STOUT ST STE 1500
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	371		WITH 300 SX CMT

\$ 121.91

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/09/2007 5:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 3700' WITH 50 SX CMT. 2ND PLUG AT 870' WITH 50 SX CMT. 3RD PLUG AT 390' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 10/09/2007 7:45 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:


1ST PLUG AT 3700' WITH 50 SX CMT. 2ND PLUG AT 870' WITH 50 SX CMT. 3RD PLUG AT 390' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

INVOICED
DATE 10/22/07
INV. NO. 2008060633

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01



Signed Eric MacLaren

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 18 2007

CONSERVATION DIVISION
WICHITA, KS

PKT