

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-21612-00-00  
Spot: E2SEW Sec/Twnshp/Rge: 15-23S-34W  
1920 feet from N Section Line, 2200 feet from W Section Line  
Lease Name: BAKER Well #: 15-8  
County: FINNEY Total Vertical Depth: 4900 feet

Operator License No.: 5214  
Op Name: LARIO OIL & GAS COMPANY  
Address: 301 S MARKET ST  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4900	1934	WITH 665 SX CMT
SURF	8.625	1828		WITH 700 SX CMT

159.25

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/09/2007 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: LARRY KARLIN Company: LARIO OIL & GAS Phone: (785) 650-2029

Proposed Plugging Method: CIBP @ 4600' OR 30 SX CMT & 500# HULLS. PLUG AT 1860' WITH 20 SX GEL - 50 SX CMT. PLUG AT 1050' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/09/2007 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 30 SX CMT & 500# HULLS. PRESSURE TO 700#. HELD AT 550#. 1ST PLUG AT 1849' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 1050' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4844	4848		
4816	4818		
4808	4814		
4730	4736		
4654	4656		

INVOICED  
DATE 10/22/07  
INV. NO. 2008060637

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed [Signature]  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 18 2007

CONSERVATION DIVISION  
WICHITA, KS

PT

[Signature]