

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.

Address: P. O. Box 783188

Phone: (316) 691-9500 Operator License #: 4767

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 09/27/2007 (Date)

by: Marvin Mills (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Lansing-Kansas City Depth to Top: 3533' Bottom: 3739' T.D. 3760'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 065-21332 -00-00

Lease Name: Montgomery B

Well Number: 1

Spot Location (QQQQ): _____ - NW - NW - NW

330 Feet from North / South Section Line

330 Feet from East / West Section Line

Sec. 8 Twp. 8 S. R. 23 East West

County: Graham

Date Well Completed: 11/17/1980 1/8/81

Plugging Commenced: 09/27/2007

Plugging Completed: 09/27/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing-Kansas City	Oil & Water	3533'	3739'	8.625"	202'	-0-
				4.50"	3784'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated at 1930', 1100' and 255' w/ 2 shots per foot. Ran tubing down to 3200'. Pumped 50 sx 60/40 Pozmix w/ 4% gel + 250 hulls. Pulled tubing up to 2200'. Pumped 75 sx 60/40 Pozmix w/ 4% gel + 200 hulls. Pulled tubing up to 1200'. Pumped 75 sx 60/40 Pozmix w/ 4% gel with 200 hulls.

Topped casing off with 30 sx 60/40 Pozmix w/ 4% gel. Pumped 20 sx 60/40 Pozmix w/ 10% gel down annulus.

Plugging complete on 09/27/2007 at 9:25 a.m., witnessed and approved by Marvin Mills with the KCC

Name of Plugging Contractor: express well service & supply inc License #: 104260

Address: P. O. Box 31 Russell, KS 67665

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.


State of Kansas County, Trego, ss.

Peter J. Fiorini - employee of Ritchie Exploration, Inc.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) P. O. Box 783188 Wichita, KS 67278-3188



SUBSCRIBED and SWORN TO before me this 8th day of October, 20 07

Notary Public

My Commission Expires: 5-4-11

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 10 2007

CONSERVATION DIVISION
WICHITA, KS

