

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Cat Energy LLC.
Address: P.O. Box 507 Galva, Kansas 67443
Phone: (620) 245-9091 Operator License #: 32778
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Mike Wilson (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-113-01380 -00-00
Lease Name: Stucky
Well Number: 2 E2HWNW
Spot Location (QQQQ): SE - NW - NW
4290 Feet from _____ North / South Section Line
4290 Feet from East / West Section Line
Sec. 4 Twp. 20 S. R. 2 East West
County: McPherson
Date Well Completed: _____
Plugging Commenced: 10-10-07
Plugging Completed: 10-12-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	155'	None
				5-1/2"	3399'	517'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.
Plugged off bottom with sand to 3280' and 5 sxs. cement. Cut casing loose @517' & layed down. Ran in 504' of 2-3/8" tubing, pumped 35 sxs. cement, pulled up to 279' and circulated 225 sxs. cement to surface. 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Cat Energy LLC.
State of Kansas County: Rice ss.

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 01 2007

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 29th day of October 20 07

Irene Herzberg
Notary Public

My Commission Expires:

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202