

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Rama Operating Co., Inc.
Address: P.O. Box 159 Stafford, KS. 67578
Phone: (620) 234-5191 Operator License #: 3911
Type of Well: SWD Docket #: D-00,222
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 10-24-2007 (Date)
by: Jeff Klock (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-159-03997-00-00
Lease Name: Fred Steckel
Well Number: 1
Spot Location (QQQQ): NE - SW - Se - Sw
680 621 Feet from North / South Section Line
1850 3603 Feet from East / West Section Line
Sec. 30 Twp. 19 S. R. 10 East West
County: Rice
Date Well Completed: 1939
Plugging Commenced: 10-25-2007
Plugging Completed: 10-26-2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Anhydrite		440	460	10 3/4	165	0
Salt		940	1,230	7	3,475	0
Arbuckle		3475	3842	5 1/2	3,380	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
Bottom plug at 3230' w/ 100 sx; Tagged top of bottom plug @ 2600 ;2nd plug at 1275' w/ 35sx; 3rd plug at 900' w/ 35sx; Top plug at 250' w/ 105 sx.
Circulated between 10 3/4 and 7"; cemented to surface. Cement was 60/40 poz, 6% Gel, .Total of 275 sk.
Topped off 5 1/2 and 10 3/4 with redi-mix 10% sand. Perforated at 1,275'; 900'; and 250'

Name of Plugging Contractor: Basic Energy Services Acid Services License #: 32453 **RECEIVED KANSAS CORPORATION COMMISSION**
Address: P.O. Box 8613 Pratt, Ks 67124

Name of Party Responsible for Plugging Fees: Rama Operating Co., Inc
State of Kansas County, Stafford, ss. **NOV 01 2007 CONSERVATION DIVISION WICHITA, KS**

Robin L. Austin of Rama Operating Co., Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
(Signature) [Signature]
(Address) P.O. Box 159 Stafford, Ks. 67578

SUBSCRIBED and SWORN TO before me this 26th day of October, 20 07
[Signature] My Commission Expires: 5-1-11
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 My Appt. Exp. 5-1-11

