

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Wilton Petroleum  
Address: Box 391, Canton, KS 67428-0391  
Phone: (620) 628-4466 Operator License #: 7775  
Type of Well: Oil Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)* *(If SWD or ENHR)*  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Doug Louis (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 113-00305-0000  
Lease Name: Myers  
Well Number: 1  
Spot Location (QQQQ): \_\_\_\_\_ - SW - SW - SE  
330 Feet from  North /  South Section Line  
2310 Feet from  East /  West Section Line  
Sec. 19 Twp. 19 S. R. 5  East  West  
County: Rice  
Date Well Completed: 12-12-54 *RECEIVED per RBDM's*  
Plugging Commenced: 10-4-05  
Plugging Completed: 10-5-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	186	
				5 1/2	3490	1270

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 3370', bailed 5 sacks cement with bailer, casing parted while pulling slips, had to cut casing head apart to get good pipe, welded slip collar on 5 1/2", ripped casing at 1270', worked pipe free, pulled casing up to 800', pumped 35 sacks, pulled to 430', pumped 35 sacks, pulled to 250', circulated with 100 sacks to surface, pulled rest of casing.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925  
Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: Wilton Petroleum

State of Kansas County, McPherson, ss.

Bernhard Runds ten (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 122 N. Main, Box 391, Canton KS 67428

SUBSCRIBED and SWORN TO before me this 18<sup>th</sup> day of October, 20 07

[Signature] Notary Public My Commission Expires: 4-4-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

