

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Tengasco, Inc.  
Address: PO Box 458 Hays, KS 67601  
Phone: (785) 625-6374 Operator License #: 32278  
Type of Well: Oil Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)* *(If SWD or ENHR)*  
The plugging proposal was approved on: 10-8-07 (Date)  
by: Herb Deines (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
LKC Depth to Top: 3509' Bottom: 3626' T.D. 3699'  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 163-21,577 - 00-00  
Lease Name: Jaco  
Well Number: #1  
Spot Location (QQQQ): SE - NW - NE -  
990 Feet from  North /  South Section Line  
1650 Feet from  East /  West Section Line  
Sec. 13 Twp. 10 S. R. 18  East  West  
County: Rooks  
Date Well Completed: 4-3-1982  
Plugging Commenced: 10-10-2007  
Plugging Completed: 10-10-2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	Oil & wtr	257'	0	8-5/8"	2-12-1982	
		3732.5'	0	4-1/4"	3-1-1982	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 2697'. Tied onto 8-5/8" csg. Pressured to 200 PSI. Tied onto tubing. Mixed & pumped 100 sx cmt /200# hulls.

Pulled tubing to 1400'. Mixed & pumped 100 sx cmt w/ 200# hulls to circ cmt to surface. Pulled tubing. Tied onto 4-1/2" csg.

Mixed & pumped 100 sx cmt w/ 100# hulls. Shut in @ 400 PSI. total cmt 300 sx 60/40 Pozmix w/ 4% gel & 500# hulls.

Name of Plugging Contractor: Chito's Well Service License #: 32028

Address: 1312 S. Washington Plainville, KS 67663

RECEIVED  
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Tengasco, Inc.


OCT 24 2007

State of KS County, Ellis, ss.

CONSERVATION DIVISION  
WICHITA, KS

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) Tengasco, Inc PO Box 458 Hays, KS 67601



SUBSCRIBED and SWORN TO before me this 15<sup>th</sup> day of October, 20 07

[Signature] Notary Public My Commission Expires: 2/5/08

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 17 2007

CONSERVATION DIVISION