

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Berexco, Inc.  
Address: PO Box 723 Hays, KS 67601  
Phone: (785) 628-6101 Operator License #: 5363  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 10-17-07 (Date)  
by: PAT STAAB (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
PAWNEE SAND Depth to Top: 4181 Bottom: 86 T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-195-21946-00-00  
Lease Name: RASE B  
Well Number: B1 *REC PRT Per CP 213*  
Spot Location (QQQQ): SE - SE - SW -  
330 Feet from  North /  South Section Line  
2970 Feet from  East /  West Section Line  
Sec. 35 Twp. 15 S. R. 21  East  West  
County: TREGO  
Date Well Completed: 1-18-88  
Plugging Commenced: 10-17-07  
Plugging Completed: 10-17-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
PAWNEE SAND	OIL	0	355'	8-5/8	1-18-88	---
		0	4299-	5-1/2" 15#	1-18-88	---

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

TIH W/ 4200' OF 2-3/8 TBG MIX 40 SKS 60/40 4% GEL W/ 3% CC & DISPLACE, PULL 15 JTS TO3750 & MIX 22 SKS GEL W/ 200# HULLS & 10 SKS CMT  
PULLED TO 1700' CIRC CMT TO SURFACE W/ 150 SKS. CMT & 200# HULLS, PULL TBG HOOK ONTO 5-1/2" CSG & SQZ 15 SKS.  
CMT TO 500' AND SHUT IN. 8-5/8 WAS FULL OF CMT.

RECEIVED  
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: EXTREME WELL SERVICE License #: 33369  
Address: PO BOX 337 ELLINWOOD, KS 67526

OCT 22 2007


CONSERVATION DIVISION  
WICHITA, KS

Name of Party Responsible for Plugging Fees: Mark Leiker w/ Berexco, Inc.  
State of KS County, ELLIS, ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mark Leiker

(Address) PO Box 723 Hays, KS 67601



SUBSCRIBED and SWORN TO before me this 18 day of OCTOBER, 20 07

Shanna Miller My Commission Expires: 9-19-09  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*PKT*