

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Mai Oil Operations, Inc.  
Address: P.O. Box 33, Russell, Ks. 67665  
Phone: (785) 483-2169 Operator License #: 5259  
Type of Well: SWD Docket #: D-25258  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 10-18-07 (Date)  
by: Bruce Baseye (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Arbuckle Depth to Top: 3699' Bottom: 3707' T.D. 3707'  
CIBP Depth to Top: 3350' Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
LKC Depth to Top: 3408' Bottom: 3433' T.D. 3350'

API Number: 15 - 051-24066-0000  
Lease Name: Giebler A *KCC PKT per RBDMS*  
Well Number: #5  
Spot Location (QQQQ): E/2 - SW - NW -  
3300 Feet from  North /  South Section Line  
4290 Feet from  East /  West Section Line  
Sec. 32 Twp. 12 S. R. 17  East  West  
County: Ellis *original spud*  
Date Well Completed: 10-24-84  
Plugging Commenced: 10-19-07  
Plugging Completed: 10-19-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0'	264'	8 5/8"	Cmtd	
		0'	3699'	5 1/2"	Cmtd	
		0'	1319'	5 1/2"	DV cmtd w/ 325	
					sks	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hookup to 5 1/2" csg. Mix 50 sks cmt. & 600# hulls, 14 sks gel & 400# hulls, 190 sks cmt, PSI to 800#, ISIP 50#, All cmt 60-40 POZ, 4% gel  
*KCCPKT*

Name of Plugging Contractor: Allied Cementing License #: 99996  
Address: 24 S. Lincoln, Russell, Ks. 67665  
Name of Party Responsible for Plugging Fees: Mai Oil Operations, Inc.  
State of Kansas County, Russell, ss.  
Allen Bangert  
(Employee of Operator) or (Operator) on above-described well, being first duly

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 24 2007  
CONSERVATION DIVISION  
WICHITA, KS

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Allen Bangert  
(Address) P.O. Box 33, Russell, Ks., 67665

SUBSCRIBED and SWORN TO before me this 22<sup>nd</sup> day of October, 2007  
Seisen Tomaseo My Commission Expires: \_\_\_\_\_  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

SEISEN TOMASEO  
NOTARY PUBLIC  
STATE OF KANSAS  
Exp. 9-10-2008

*PKT*