

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: R.R. Abderhalden
Address: 100 S. Main, Suite 510, Wichita, Kansas 67202
Phone: (316) 262-3411 Operator License #: 5394
Type of Well: oil/gas KCC PRT per CPS 13 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 9-12-07 (Date)
by: Duane Krugger (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Stalnaker Depth to Top: 1854 Bottom: 1992 T.D. _____
Kansas City Depth to Top: 2432 Bottom: 2492 T.D. _____
Mississippi Depth to Top: 3046 Bottom: 3140 T.D. 3150

API Number: 15 - 035-20898 ~~00-00~~
Lease Name: Werner
Well Number: 3
Spot Location (QQQQ): _____ - NE - SW - SE
990 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 31 Twp. 32 S. R. 6 East West
County: Cowley
Date Well Completed: 11-28-75
Plugging Commenced: 9-12-07
Plugging Completed: 9-27-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	170	-0-
				4 1/2	3149	1649

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Dumped 105 gals. sand and 5 sax cement on bottom. Plugged well back to 1890 ft.
Dumped 60 gals, sand at 1890. Dumped 4 sax cement on sand. Shot at 1649 ft. and pulled casing. Ran tubing to 350 ft. and cemented with 130 sax to surface.

Name of Plugging Contractor: R.R.A., Inc. License #: 5656 **RECEIVED**
Address: 100 S. Main, Suite 510, Wichita, Kansas 67202 KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: R.R. Abderhalden **OCT 24 2007**
State of Kansas County, Sedgwick, ss. **CONSERVATION DIVISION WICHITA, KS**
R.R. Abderhalden (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) R.R. Abderhalden
(Address) 100 S. Main, Suite 510, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 24 day of October, 2007
Verdelia Lewis My Commission Expires: 6-6-10
Notary Public

Handwritten initials

Operator R. R. Abderhalden

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Oil

Well No.

3

Lease Name

Werner

Oil Well

S 31 T 32 R 6 E
XX

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Iatan 1832

Stalnaker 1854

Layton 2307

Kansas City 2432

Miss. Chert 3046

Induction Electrical Log

Compensated Density Log

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 24 2007

CONSERVATION DIVISION
WICHITA, KS

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

R. R. Abderhalden

Signature

Owner

Title

8-30-76

Date