

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: JOHN O. FARMER, INC.
 Address: P.O. Box 352 Russell, KS 67665
 Phone: (785) 483-3144 Operator License #: 5135
 Type of Well: D & A Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 8/31/07 (Date)
 by: Richard Lacey (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (if needed attach another sheet)
None Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 135-24, 688-0000
 Lease Name: GABEL
 Well Number: 1
 Spot Location (QQQQ): NW - NW - SE - NE
1330 Feet from North / South Section Line
1290 Feet from East / West Section Line
 Sec. 25 Twp. 17 S. R. 25W East West
 County: Ness
 Date Well Completed: 9/4/07
 Plugging Commenced: 11:30AM 9/4/07
 Plugging Completed: 2:00PM 9/4/07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	211'	8 5/8"	210.94'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug @ 1740'W/50sks 5th Plug @ 60'W/20sks Circulated 1st Plug 15 Minutes W/58 Vis Mud
2nd Plug @ 1030'W/80sks 15sks In Rat Hole Plugs displaced with mud
3rd Plug @ 600'W/40sks 10sks In Mouse Hole Total 255sks 60/40Poz 4%GelW/1/4#CF/sk
4th Plug @ 240'W/40sks By Allied Cementing- Completed @ 2:00PM 9/4/07

Name of Plugging Contractor: Discovery Drilling Co., Inc. License #: 31548
 Address: P.O. Box 763 Hays, KS 67601
 Name of Party Responsible for Plugging Fees: JOHN O. FARMER, INC.
 State of Kansas County, Russell, ss.

John O. Farmer III (Employee of Operator) or (Operator) on above described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) John O. Farmer III
 (Address) P.O. Box 352, Russell, KS 67665


RECEIVED
KANSAS CORPORATION COMMISSION

OCT 24 2007
CONSERVATION DIVISION
WICHITA, KS

SUBSCRIBED and SWORN TO before me this 23rd day of October, 20 07

Margaret A. Schulte
Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten signature]