

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 26 2007
CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003
File or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oil Producers Inc. of Kansas
Address: 1710 Waterfront Parkway, Wichita, KS 67201
Phone: (316) 681-0231 Operator License #: 8061
Type of Well: Oil & Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 145-21560-0000
Lease Name: Schartz *KCC*
Well Number: 5A-7 *PKT Per CP2/B*
Spot Location (QQQQ): NE - NE - NE
660 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 7 Twp. 23 S. R. 16 East West
County: Pawnee
Date Well Completed: 8-07
Plugging Commenced: 9-25-07
Plugging Completed: 9-27-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	509	
				4 1/5	4367	<i>2470 2240</i>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Sand at 4110', bailed 4 sacks cement with bailer, ripped casing at 3210', worked pipe, ripped casing at 3050', worked pipe, left on tension, pipe wasn't free, ripped casing at 2840', worked pipe, ripped casing at 2630', ripped casing at 2470', pipe came free, pulled up to 1100', pumped 15 gel, 50 sacks, pulled to 520', pumped 50 sacks, pulled to 40', pumped 20 sacks to surface, tore down floor and rig, emptied pit.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: Oil Producers Inc. of Kansas

State of Kansas County, Sedgwick, ss.

Oil Producers Inc. of Kansas (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]

(Address) 1710 Waterfront Parkway, Wichita, KS 67206

SUBSCRIBED and SWORN TO before me this 16th day of October, 2007

Louie A. Zehr My Commission Expires: May 5, 2010
Notary Public

PKT