

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-181-20266 ⁰⁰⁻⁰⁰

COUNTY Sherman

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.
TYPE OR PRINT

LEASE NAME Hendrich WELL# 1-7

SPOT LOCATION NE NW

LEASE OPERATOR Goodland Gas Company

SEC. 7 TWP. 8s RGE. 39 (E) OR (W)

PHONE # () 713/ 850-0558

OPERATORS LICENSE NO. _____

CHARACTER OF WELL Gas (OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DATE WELL COMPLETED 11-17-83 PLUGGING COMMENCED 11-17-83

PLUGGING COMPLETED 11-17-83 REASON FOR ABANDONMENT OF WELL OR PRODUCING

FORMATION- Not commercial production

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? District 6 913/ 628-1200

Is ACC-1 FILED? Attached IF NOT, IS WELL LOG ATTACHED? N/A

PRODUCING FORMATION Niobrara DEPTH TO TOP 1125 BOTTOM T.D. 1342

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		345	0	7"	345'	N/A

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Total of 100 sacks cement 50/50 Pozmix 6% gel 3% CC as follows: (1) 25 sacks @ 1320'; (2) 25 sacks @ 1180'; (3) 40 sacks @ 400'; (4) @ 40' dumped 1 sack lime & 1 sack cotton hulls; (5) 10 sacks @ 40'-surface

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Halliburton Services LICENSE No. 5287

ADDRESS P. O. Box 47

Oberlin, Kansas 67749

STATE OF Texas COUNTY OF Harris, SS.

Suzanne Parks (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT. SO HELP ME GOD.

(SIGNATURE) Suzanne Parks

(ADDRESS) 1111 Fannin, Suite 1602 Houston, Texas 77002

SUBSCRIBED AND SWORN TO BEFORE ME THIS 29 DAY OF December, 19 83

AMELIA SOILEAU
Notary Public, State of Texas
My Commission Expires December 23, 1987
Bonded by Lovett Agency, Lawyers Surety Corp.

Amelia Soileau
NOTARY PUBLIC

MY COMMISSION EXPIRES: _____

Rec'd
1-10-84

FORM CP-4
REVISED 06-83

15-181-20266-00-00

KCC/KDHE JOINT OIL/GAS REGULATORY OFFICE

DATE November 22, 1983.

- New Situation
- Response to Request
- Follow-up

OPERATOR _____ # _____

NAME & ADDRESS _____

LOCATION NW, SEC 7, T 8 S, R 39 W

LEASE Hendrich Well # 1-7

PHONE NO. OPER. _____ OTHER _____

COUNTY Sherman

REASON FOR INVESTIGATION: _____

PROBLEM: _____

PERSON(S) CONTACTED: _____

FINDINGS: I plugged this well on 16-11-83 the following information was given to me; by James Browning.
operator - J.W. operating, contractor Western Well Drllg Co., James Browning consultant with Cross operating Co.
- Carl Goodrow is working on this and will follow up with a report.
Note intent to drill attached.

ACTION/RECOMMENDATIONS: _____

photos taken: _____

Retain 1 copy Joint District Office
 Send 1 copy Conservation Division
 Send 1 copy KDHE/Topeka if appropriate

NOV 26 1983

By Del L. Battagor

LEASE INSPECTION

COMPLAINT

FIELD REPORT

