

15-143-00005-00-00

WELL PLUGGING RECORD

OR


FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

Ottawa County Sec. 29 Twp. 9 Rge. (E) 1 (W) Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW NW NE Lease Owner Westgate-Greenland Oil Company Lease Name Foote Well No. 1 Office Address 1022 Union National Bank Building Character of Well (completed as Oil, Gas or Dry Hole) dry hole Date well completed April 25, 1949 Application for plugging filed orally-April 25, 1949 Application for plugging approved April 25, 1949 Plugging commenced April 25, 1949 Plugging completed April 25, 1949 Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee Producing formation Depth to top Bottom Total Depth of Well Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Surface, 0, 158, 8 5/8", 158 feet, none.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from total depth to 158 feet Set plug @ 158 and dumped in 20 sacks cement. Filled hole to 15 feet with heavy mud and run 5 sacks cement to cellar base

5-2-49

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Westgate-Greenland Oil Company c/o G. E. Bitler Address 1022 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick G. E. Bitler (employee of owner) or owner of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. (Signature) G. E. Bitler 1022 Union National Bank Building, Wichita 2, Ks (Address)


SUBSCRIBED AND SWORN to before me this 2nd day of May, 19 49

Signature of Notary Public: Esther Russell

Notary Public.

My commission expires May 25, 1949

22-2625 2-48-15M



COMPANY: Westgate-Greenland Oil Company  
 CONTRACTOR: Mallard Drilling Company  
 Farm: Foote #1  
 LOCATION: NW NW NE/4 Section 29-9-1W  
 Ottawa County, Kansas  
 COMMENCED: April 12, 1949  
 COMPLETED: April 25, 1949

0	to	158	Surface sand
158	to	300	Shale and lime
300	to	530	Shale and lime
530	to	730	Sandy lime
730	to	885	Sandy lime and shale
885	to	915	Sand and red bed
915	to	1170	Shale and shells
1170	to	1490	Shale and shells
1490	to	1730	Shale and lime
1730	to	1940	Lime and shale
1940	to	2100	Shale and lime
2100	to	2270	Lime
2270	to	2590	Lime and shale
2590	to	2660	Shale and lime
2660	to	2783	Lime and chert
2783	to	2863	Lime and Shale
2863	to	3078	Lime and shale
3078	to	3173	Lime
3173	to	3338	Shale and lime
3338	to	3613	Lime
		3613	T.D.

Set 158 feet of 8 5/8" surface pipe. Cemented with 100 sacks cement.  
 Surface pipe 2 1/4" new pipe.

FOPS: Lansing --2098      Mississippi--2660      Hunton--2980      Viola--3330  
 Simpson--3464      Arbuckle--3568

Measurements from derrick floor.

DRY, ABANDONED AND PLUGGED

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Foote #1, Section 29-9-1W, Ottawa County, Kansas, as reflected by files of the Mallard Drilling Company.

*C. C. Nelson*

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 2nd day of May 1949.

*Harwell Wright*

My commission expires 12/4/54

RECEIVED 5-2-49  
 Conservation Div.  
 MAY 2 - 1949  
 STATE DEPARTMENT  
 COMMISSION

DRILLING  
 29-9-1W  
 93