


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-123-00011-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Mitchell County. Sec. 20 Twp. 9S Rge. 9W ~~(W)~~ (W)
Location as "NE/CNW/SW" or footage from lines C SW NW
Lease Owner Tryng Nagel & National Drilling Company, Inc.
Lease Name Schneider Well No. 1
Office Address 535 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 8, 1961
Application for plugging filed January 9, 1961
Application for plugging approved January 9, 1961
Plugging commenced January 9, 1961
Plugging completed January 9, 1961
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,126 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	195'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with Rotary Mud to 190 feet. Cemented with 20 sacks cement thru drill pipe. Mudded hole to 40 feet, cemented to top.

CONSERVATION DIVISION
Wichita, Kansas

1-16-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor National Drilling Company, Inc.
Address 535 Petroleum Building, Wichita, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Howard A. Stoskopf, (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Howard A. Stoskopf
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of January, 19 61

My commission expires December 3, 1964.
Geraldine Hays
Geraldine Hays, Notary Public.



15-123-00011-00-00


KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **LOYD G. ANGEL & PARTNERS, DRILLING DRUGS COMPANY, INC.**
FARM **Schneider** NO. **1**

SEC. **20** T. **90** R. **90**
LOC. **0 SW 1/4**

TOTAL DEPTH **4126'**
COMM. **12-30-60** COMP. **1-9-61**
SHOT OR TREATED
CONTRACTOR **National Drilling Company, Inc.**
ISSUED

COUNTY **Mitchell**
KANSAS



CASING
20 10 1/4" 195' con. w/150 sz.
15 8
12 6
13 5

ELEVATION **1657** **67**
1659 **67**
1662 **60**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

surface clay	25		
shale & shells	195	salt	1060 to 1130
shale & sand	488	Ft. Riley	1475 - 187
shale & shells	550	Howard	2441 - 779
sand	600	Popoka	2476 - 814
red bed & shale	1190	Keokuk	2720 - 1058
shale & shells	1350	Lansing	2800 - 1138
lime & shale	1925	Case K.O.	3139 - 1477
shale & shells	2412	Cherokee Sh.	3276 - 1614
shale & lime	2475	Mississippi	3412 - 1750
lime	2500	Kinderhook	3624 - 1962
lime & shale	2848	Hanton	3670 - 2008
lime	3140	Maquoketa	3708 - 2046
shale & lime	3450	Viola	3794 - 2132
lime & chert	3510	Simpson	4000 - 2338
Mississippian	3580	Arbuckle	4067 - 2405
lime & shale	3850	RED	4126 - 2464
lime	4085		
lime & shale	4070		
lime	4126		
Rotary Total Depth	4126		

I hereby certify that the above is a true and correct log of the above described well as shown by the drilling reports.

LOYD G. ANGEL & PARTNERS, INC

Howard A. Stoskopf
Howard A. Stoskopf, President

STATE OF KANSAS)
COUNTY OF MITCHELL)

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 11th day of January, 1961.

Seraldine Hays
Seraldine Hays, Notary Public

My Commission Expires
December 3, 1964

STATE OF KANSAS
JAN 11 1961
COUNTY OF MITCHELL
Wichita

1-16-61