

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-141-203040000

LEASE NAME DeMoss

WELL NUMBER 1

2,970 Ft. from S Section Line

330 Ft. from <sup>W</sup>~~E~~ Section Line

SEC. 6 TWP. 9 RGE. 11 (~~E~~) or (W)

COUNTY Osborne

Date Well Completed 10-26-95

Plugging Commenced 10-26-95

Plugging Completed 10-26-95

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Brungardt Oil & Leasing Co.

ADDRESS PO Box 871, Russell, Kansas 67665

PHONE#(913) 483-4975 OPERATORS LICENSE NO. 3956

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-26-95 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3,420'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	216'	Cmtd. w/135 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Push bridge plug to 1,000', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 775', pump 100 sax cement on plug thru drill pipe. Push bridge plug to 270', pump 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co.

License No. 5184

Address PO Box 709, Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brungardt Oil & Leasing

STATE OF KANSAS COUNTY OF RUSSELL

Jack P. Beeman

(Employee of Operator or Operator) of  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,  
statements, and matters herein contained and the log of the above-described well as filed that  
the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec - Treas


(Address) PO Box 709  
Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 8th day of November, 19 95

My Commission Expires: \_\_\_\_\_



Ruth Phillips  
Notary Public



# Shields


15-141-20304-00-00

Russell, Kansas

## WELL LOG

Operator: Brungardt Oil & Leasing Co.  
 Well: DeMoss #1  
 Commenced: October 18, 1995  
 Completed: October 26, 1995  
 Contractor: Shields Drilling Co.

Well Description: SW SW NW  
 Sec. 6-9S-11W  
 Osborne Co., Kansas



Elevation: 1,871' KB

Treatment:

Production: D & A

Tops:

### CASING RECORD

Size	Run	Pulled
8 5/8"	216'	Cmtd. w/135 sax

..... Figures Indicate Bottom of Formations .....

Rock & shale	150'
Shale & sand	976'
Anhydrite	1,005'
Shale	1,455'
Shale & lime	2,890'
Lime	3,420' RTD

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 NOV 09 1995  
 CONSERVATION DIVISION  
 WICHITA, KS

Notes