

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-141-203170000

LEASE NAME DeMoss

WELL NUMBER 2

990' Ft. from <sup>N</sup> Section Line

330' Ft. from <sup>W</sup> Section Line

SEC. 6 TWP. 9 RGE. 11 (X) or (W)

COUNTY Osborne

Date Well Completed 6-27-96

Plugging Commenced 6-27-96

Plugging Completed 6-27-96

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Brungardt Oil & Leasing Co.

ADDRESS PO Box 871, Russell, KS. 67665

PHONE#(913) 483-4975 OPERATORS LICENSE NO. 3956

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-27-96 (date)

by David Wann (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3,095'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	214'	Cmtd. w/135 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. Push bridge plug to 915', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 700', pump 80 sax cement on plug thru drill pipe. Push bridge plug to 200', pump 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brungardt Oil & Leasing Co.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman (Employee of Contractor or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

7-17-96  
RECEIVED  
STATE CORPORATION COMMISSION

(Signature) Jack P. Beeman, Sec - Trust

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 16th day of July, 19 96

My Commission Expires:



Notary Public




Shields 15-141-20317-00-00  
Russell, Kansas

WELL LOG

Operator: Brungardt Oil & Leasing Co.  
Well: DeMoss #2  
Commenced: June 21, 1996  
Completed: June 27, 1996  
Contractor: Shields Drilling Co.

Well Description: SW NW NW  
Sec. 6-9S-11W  
Osborne Co., Kansas



CASING RECORD  
Size Run Pulled  
8 5/8" 214' Cmtd. w/135 sax

Elevation: 1,811' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations .....

Rock & shale	214'
Shale & sand	885'
Shale	911'
Anhydrite	946'
Shale	2,530'
Shale & lime	3,030'
Lime	3,095' RTD

Notes

RECEIVED  
STATE CORPORATION COMMISSION

JUL 17 1996

STATE CORPORATION COMMISSION  
WICHITA, KANSAS